

DRIVEWAYS AND SIDEWALKS

ALL DRIVEWAY ADDITIONS MUST HAVE APPROACHES ADDED.

APPROACHES

BASE MATERIAL - 4 INCHES PEA GRAVEL, COMPACTED

6 INCHES OF CONCRETE, 4,000 PSI

EXPANSION JOINTS REQUIRED AT CURB AND SIDEWALK.

CONCRETE DRIVEWAYS

BASE MATERIAL - 4 INCHES PEA GRAVEL, COMPACTED

4 INCHES CONCRETE, 4,000 PSI

EXPANSION JOINTS AT GARAGE OR HOUSE

SIDEWALKS AT DRIVEWAYS

BASE MATERIAL - 4 INCHES GRAVEL, COMPACTED

6 INCHES CONCRETE, 4,000 PSI

PATIO AND SIDEWALKS

BASE MATERIAL - 4 INCHES GRAVEL, COMPACTED

4 INCHES CONCRETE, 4,000 PSI

ASPHALT DRIVEWAYS - RESIDENTIAL

BASE MATERIAL - 6 INCHES CRUSHED LIMESTONE, COMPACTED

2 INCHES ASPHALT

ASPHALT DRIVEWAYS - COMMERCIAL

BASE MATERIAL - 8 INCHES OF CRUSHED LIMESTONE, COMPACTED

3 INCHES OF ASPHALT